

Section 14420

Typical Hydraulic Vertical Platform Lift Specifications

1.0 GENERAL

RELATED DOCUMENTS :

Drawings and general provisions of the Contract, including instructions to Bidders, Supplementary instructions to Bidders, General Conditions, Specification Sections apply to work of this Section.

DESCRIPTION :

- A. Work described in this section includes providing equipment, incidental material and labor required for complete, operable hydraulic platform lift installation. Where singular reference is made to lifts or lift components, such reference shall apply to number of lifts or components required to complete installation. This specification provides a broad outline of required equipment and does not describe the details of design and construction. Lifts shall be erected, installed, adjusted, tested and placed in operation by lift system manufacturer, or manufacturer's authorized installer.
- B. Lifts shall be in accordance with the ASME A18.1 and ADA compliant including local codes and regulations except where specified otherwise.
- C. The lift described here, APEX 750 from Nationwide Lifts, Inc, is a vertical platform lift consisting of a hydraulic tower with a lifting platform. The platform can be customized to better accommodate a wheelchair user or a person with impaired mobility. The lift can be used indoor or outdoor (with optional package) and in commercial and residential applications.

1.2 PREPARATORY WORK BY OTHERS :

- A. The following preparatory work to receive the lifts specified in this section is part of the work by others :
 - 1. Permanent 120 VAC, 20 amp single phase power to operate lift to be provided from a lockable fused/cartridge type disconnect switch with auxiliary contacts for battery operation. Refer to drawings for permanent power specifications and location of disconnects. Temporary power may be provided to expedite installation of lift.
 - 2. Provide a plumb and square hoistway with smooth interior surfaces, including fascias or furring of the hoistway interior.
 - 3. Provide rough openings per lift contractor's shop drawings.
 - 4. Provide substantial, level pit floor slab as indicated on the lift contractor's shop drawings.

1.3 QUALITY ASSURANCE :

- A. MANUFACTURER
Company with not less than 20 years of experience in the design, fabrication and assembly of vertical platform lifts.
- B. SUBCONTRACTOR QUALIFICATIONS :
 - 1. Execute work of this section only by a company that has adequate product liability insurance.
 - 2. Skilled tradesmen must be employees of the installing contractor approved by the lift manufacturer, with demonstrated ability to perform the work on a timely basis.
- C. REQUIREMENTS OF REGULATORY AGENCIES :
 - 1. Fabrication and installation work in compliance with applicable jurisdictional authorities.
 - 2. File shop drawings and submissions with local authorities as the information is made available. Company pre-inspection and jurisdictional authority inspections and permits are to be made on timely basis as required.
- D. SUBMITTALS :
 - 1. Shop drawings shall show a complete layout of lifting equipment detailing dimensions and clearances as required.

2. The lift contractor shall provide physical samples of all items requiring selection of color or finish.

1.5 MAINTENANCE

A. The lift shall be cleaned regularly and inspected at intervals no longer than every 6 months.

1.6 WARRANTY:

A. A warranty of 30 months on parts shall be offered by the lift manufacturer.

2.0 PRODUCTS

2.1 PLATFORM LIFT :

A. Basic of specification of Nationwide Lifts hydraulic vertical platform lift model APEX 750:

1. Rated Load.....750 lb (340 kg)
2. Rated Speed.....25 f.p.m.(nominal) (0.13 m/s)
3. Usable Car Dimensions.....34'' x 54'' (864 X 1,372 mm)
4. Levels Serviced.....2,3,4
5. Number of Openings.....2
6. Car Access.....Enter/Exit same side, 90° exit, front/rear
7. Max. Travel.....23 feet (7,000 mm)
8. Operations.....Constant pressure
9. Power Supply110 volt, 15 amp, 1 phase, 60 Hz
10. Drive System.....2:1 Roller chain hydraulic
11. Paint.....Powder coat finish
12. Emergency Power.....Battery operation in down direction
13. Controller.....Electronic-free relay logic
14. Motor/Pump.....110VAC, 1.5HP
15. Manual lowering.....Outside the hoistway at desired landing
16. Color.....Almond beige

B. CAR ENCLOSURE

1. Side guards of platform shall have a steel frame with a powder coat finish and steel panel inserts to a minimum of 42'' (1,067 mm) above the upper landing.
2. No platform gate required, to allow for ease of operation.
3. Upper gate shall be 42'' high x 36'' wide, with metal or plexiglass inserts and shall be equipped with interlock, spring hinges and kick plate. Lower door shall be 80'' high x 36'' wide, with metal or plexiglass inserts and shall be equipped with interlock hydraulic closer and kick plate on both sides. The inside kick plate shall be made of steel.
ALTERNATE A: 36'' wide x 80'' high top landing door instead of the top landing gate.
ALTERNATE B: Lower and upper door and door frame with 1 1/2 hour ULC Fire rating, heavy duty hinges, Door vision panel, flush mounting of door inside the hoistway and adjustable hydraulic door closer on door frame
4. Lift shall have manufacturer's standard non-skid flooring.
5. Doors and gates shall be flush mounted inside the hoistway as to avoid pinch points and shear hazards.
6. Handrail : A single handrail with both ends returned to the side guard shall be located on the control wall of the carriage.

2.2 CAR OPERATION :

- A. Car Operating Panel shall consist of constant pressure buttons or rocker switches, emergency stop/alarm button, on/off key switch and emergency light mounted on a removable stainless steel panel (Type 304 #4 Stainless Steel Finish).
- B. Emergency Operation — The car shall be equipped with a battery operated light fixture, emergency battery lowering device and alarm in case of normal building supply failure. The battery shall be the rechargeable type with an automatic recharging system. A manual lowering device shall be located outside the hoistway in a lockable box at positioned at a designated landing.

2.3 PUMPING UNIT AND CONTROL :

- A. The pumping unit and control shall be enclosed in the tower. The controller and pump unit shall be pre-wired and tested prior to shipment. The controller is to be electronic-free with relay logic operation for ease of maintenance and service. Pump unit shall incorporate the following features :
 1. Smooth stops at each landing.
 2. Adjustable pressure relief valve.
 3. Manually operable down valve to lower lift in the event of an emergency. This valve shall be activated from outside of the hoistway through a keyed box.
 4. Pressure gauge isolating valve, manually operable.
 5. Gate valve to isolate cylinder from pump unit.
 6. Electrical solenoid for down direction control.
 7. Emergency lowering by battery power, from the car control.

2.4 CYLINDER AND PLUNGER :

- A. The cylinder shall be constructed of steel pipe of sufficient thickness and suitable safety margin. The top of the cylinder shall be equipped with a cylinder head with an internal guide ring and self-adjusting packing.
- B. The plunger shall be constructed of a steel shaft of proper diameter machined true and smooth. The plunger shall be provided with a stop electrically welded to the bottom to prevent the plunger from leaving the cylinder.

2.5 ROLLER CHAINS :

- A. Two (2) No.50 roller chains with 5/8" pitch. Minimum breaking strength 6100 lb (2773 kg) each

2.6 LEVELLING DEVICE :

- A. The lift shall be provided with an anti-creep device which will maintain the carriage level within 1/2" (12.69 mm) of the top landing.
- B. All limit switch and leveling device switches shall be located in a position to be inaccessible to unauthorized persons. They shall be located behind the mast wall and be accessible through removable panels.

2.7 GUIDE YOKE :

- A. The 2:1 guide yoke/sprocket assembly shall be supplied with two (2) sprockets, roller guide shoes, bearings and guards.

2.8 CALL STATIONS :

- A. Provide door frame mount key-controlled call stations for upper level and lower level on a stainless steel plate (Type 304 #4 stainless steel finish).

2.9 TERMINAL STOPPING DEVICES:

- A. Normal terminal stopping devices shall be provided at top and bottom of runway to stop the car positively and automatically. Microswitches shall not be used.

2.10 GUIDE RAILS AND BRACKETS :

- A. Steel "C" guide rails and brackets shall be used to guide the platform and sling. Guide rails shall form part of the structural integrity of the unit and be integral to the mast enclosure, ensuring stability and minimum platform deflection when loaded.

2.11 CAR SLING :

- A. Car sling shall be fabricated from steel tubing 44'' (1,116 mm) high with adequate bracing to support the platform and car enclosure. Roller guide shoes shall be mounted on the top and bottom of the car sling to engage the guide rails. Guide shoes shall be roller type with 3'' diameter wheels.

2.12 WIRING :

- A. All wiring and electrical connections shall comply with applicable codes. Insulated wiring shall have flame-retardant and moisture-proof outer covering and shall be run in conduit or electrical wireways if located outside the unit enclosure. Quick disconnect harnesses shall be used when possible.

2.13 DOOR LOCKS

- A. The door locks shall be GAL type "N" interlock or fire rated electric door strike conform to ASME A18.1 b 2000.

2.14 DOORS AND GATES

- A. LOW-PROFILE ALUMINUM (TOP OR BOTTOM LANDINGS)

This door shall have a flush-mounted door frame, an hydraulic door closer, a vision panel and a handle. Fire-rated electric door strike or GAL interlock shall be used.

- B. TOP LANDING GATE

This gate is installed on the top landing and shall be used with a fire-rated electric door strike or a GAL interlock. The size shall be 42'' high and it shall be provided with metal or acrylic insert.

3.0 EXECUTION :

- A. EXAMINATION : All site dimensions shall be taken to ensure that tolerances and clearances have been maintained and meet local regulations.
- B. PREPARATION : Pre-inspect the construction and service requirements for work by others. These requirements will be included in drawings, diagrams, engineering data sheets and special instructions before the work begins.
- C. INSTALLATION :
 1. Install all the components of the lift system that are specified in this section to be provided, and that are required by jurisdictional authorities to license the lift.
 2. Trained employees of the lift contractor shall perform all installation work of this section.
 3. Adjust lift for proper operation and clean unit thoroughly.
 4. Instruct users in operation procedures and Owner's maintenance person in trouble-shooting and maintenance procedures.

END OF SECTION.